


THE
SPRING
2013
FLEET
ADDITIONS
UPDATE

SETTING SAIL

OVER THE NEXT TWO YEARS DIAMOND OFFSHORE WILL LAUNCH FOUR ULTRA-DEEPWATER DRILLSHIPS AND TWO DEEPWATER SEMISUBMERSIBLE RIGS. THREE OF THE RIGS ALREADY HAVE CONTRACTS AND WILL HEAD DIRECTLY TO WORK.





ULTRA-DEEPWATER DRILLSHIPS

OCEAN BLACKHAWK CONTRACT ANADARKO

OCEAN BLACKHORNET CONTRACT ANADARKO

OCEAN BLACKRHINO

OCEAN BLACKLION



GENERAL	<p>Design: Gusto P10,000</p> <p>Classification: ABS</p> <p>Dimensions: 754 ft long x 118 ft wide x 59 ft deep</p> <p>Draft: 36 ft operating / 29 ft transit</p> <p>Displacement: 70,455mT operating</p> <p>Variable Deck: 22,045T operating</p> <p>Transit Speed: up to 12.5 knots</p> <p>Water Depths: 12,000 ft designed / 10,000 ft outfitted</p> <p>Drilling Depth: 40,000 ft</p>
DRILLING	<p>Derrick: NOV Dual Bottleneck, 210 ft high with 80 ft x 60 ft base, static hook load capacity of 4,000 kips</p> <p>Drawworks: (Main): NOV / AHD 1250-9000, six AC electric motors, 9,000hp each, 1,250T with sixteen 2 1/8" drilling lines (Aux): NOV / AHD 750-5750, five AC electric motors, 5,750hp each, 750T with fourteen 1 3/4" drilling lines</p> <p>Compensator: Active Heave Compensating Drawworks</p> <p>Rotary Table: (Main): NOV RST 75 1/2" hydraulic, 1,250T (Aux): NOV RST 60" hydraulic, 1,000T</p> <p>Top Drive: (Main): NOV TDX-1250, 1,250T with 7,500 psi (Aux): NOV TDS-8SA, 750T with 7,500 psi</p> <p>Tubular handling: 2 x NOV MPT 'Hydraulic Roughneck' for tubular range 3 1/2" to 9 3/4" + 2 x NOV PRS-5</p> <p>Mud Pumps: 5 x NOV 14-P-220, 2,200hp, 7,500 psi</p>
POWER	<p>Main Power: 6 x HHI Himsen V- type diesel engines rated 4,500hp, each driving 5,375 kVA AC generators 2 x HHI Himsen V-type diesel engines rated 9,000hp, each driving 10,875 kVA AC generators</p> <p>Emergency Power: V-type diesel engine rated 1,500hp driving 1,875 kVA AC generator</p>
STORAGE	<p>Liquid Mud: 23,500 bbls</p> <p>Base Oil: 9,225 bbls</p> <p>Brine: 10,000 bbls</p> <p>Drill Water: 22,500 bbls</p> <p>Potable Water: 11,750 bbls</p> <p>Bulk Material: 7,500 bbls (mud + cement)</p> <p>Sack Storage: 6,000 sacks</p>
CRANES	<p>Knuckle-boom: 110 ton + 2 x 90 ton knuckle-boom</p> <p>AHC Subsea: 180 ton Active Heave Compensation knuckle-boom</p>
SUBSEA	<p>Diverter: Vetco CSO 21" 500 psi diverter with 16" flow line</p> <p>BOP Stacks (2): Hydril 18 3/4" 15,000 psi seven-ram preventer 2 x Hydril 18 3/4" 10,000 psi annular preventers</p> <p>C&K Manifold: 3 1/16", 15,000 psi</p> <p>Marine Riser: Vetco HMF Class H 21", 75 ft long per joint</p> <p>Tensioners: 16 x 225 kips NOV wireline riser tensioners. Total capacity 3,600 kips with 50 ft of wire travel</p> <p>Moonpool: 73 ft x 41 ft</p>
OTHER	<p>Thrusters: 6 x (three forward, three aft) Thrustmaster variable speed, fixed pitch, fully azimuthing</p> <p>DP System: Kongsberg DPS-3</p> <p>Dual Activity: Yes</p> <p>Accommodation: 210 people</p> <p>Helideck: Sikorsky S-61 & S-92</p>

MILESTONES TO COMPLETION

SHIPYARD DELIVERY DATES

1Q 2013

2Q 2013

3Q 2013

OCEAN BLACKHAWK

CONTRACT
ANADARKO

OCEAN ONYX

CONTRACT
APACHE

